TUMKUR DIVISION.

Notice dated 28th December 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 1 P.M., on the 28th January 1928, for constructing Sub-Register's Office and Bonded Warehouse at Kunigal. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 30th June 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M., on all days except Sunday and Holidays.

3. The tenders should be submitted on printed forms which may be obtained from the Executive Engineer.

4. Each tender must be accompanied by a deposit of Rs. 350 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Sub-Registrar's Office and Bonded Warehouse at Kunigal" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. The rate should be noted both in figures and in words in the form without any corrections or additions.

10. No claim for any higher rate on any account will be entertained after the tender is accepted.

11. The contractor will be dealt with in terms of his bond for any short progress or delay.

12. In matters of all disputes about rates and measurements quality of work, etc., and in all disputes of any kind the decision of the Chief Engineer will be final and legally binding.

Approximate quantities of work for constructing Sub-Registrar's Office and Bonded Warehouse at Kunigal.

S. No.	Items of work	Per	Quantity
1	Earthwork excavation and filling in basement ...	C.yds	54
2	Burnt stone in clay	C.ft.	1909
3	Burnt brick in clay	,,	2534
4	Burnt brick in mortar	,,	565
5	Burnt stone slabs 6" thick one line dressed ...	S.ft.	607
6	Chunam plastering, two coats	Sqr.	60·55
7	Chunam pointing nice	,,	3·46
8	White and colour washing, two coats	,,	60·55
9	Teakwood work with wood oiling	C.ft.	165·03
10	Roofing with 1st Class Mangalore pattern Tumkur tiles on teak reepers and eave tiles being tied up with teak batton screw down to the rafters, etc., complete.	Sqr.	17·60
11	Ridge tiles set in mortar and cement pointing ...	R.ft.	52
12	Chunam borders, 6" thick	,,	144
13	Flat terrace roofing with terrace brick on edge 3" concrete and three courses of flat tiles and plaster.	Sqr.	6·07
14	Burnt brick in chunam cornice 9" thick including smooth plastering with mortar.	R.ft.	257
15	Teakwood ornamental eave board 9" wide including painting.	,,	113
16	Cutting channels in carbel stones and stone slab	No.	28

Sl. No.	Items of work	Per	Quantity
18	Teakwood doors 1¼″ thick with panelled shutters with iron clamps, iron works such as hinges, tower bolts, pad-locks, etc., complete.	S.ft.	114
19	Teakwood doors, 1½″ thick with battened shutters, with four folded iron clamps, hinges, tower bolts, pad locks, etc., complete. The side frame to be fixed in cill slab in 3″ depth to fix the frame.	,,	44
20	Teakwood windows with expanded metal one inch mesh quarter inch thick outside fixed, inside glazed shutters with iron bars ¾″ dia. fastenings, hinges, etc., complete to Sub-Registrars' Clerks' and record rooms.	,,	95
21	Teakwood windows with panelled shutters outside and inside glazed ¾″ dia. iron bars with iron clamps, hinges, etc., complete.	,,	157
22	Teakwood ventilators with expanded metal of one inch mesh and quarter inch thick, the shutters fixed to frame and iron bars and clamps, etc., complete.	,,	21
23	Teakwood finials at gable ends 4′ long 4″×4″ ...	No.	2
24	Silicate chocolate paint	Sqr.	12·84
25	Flooring with 1½″ thick Cuddapah slabs over 3″ concrete bed and cement pointing.	,,	12·06
26	Flooring with burnt stone slabs, 4½″×6″ thick over 6″ sandbed and cement pointing to spirit room.	,,	2·64
27	Expanded metal (1″ mesh and ¼″ thick) partition with four folded shutters with teak frame 2″×3″ with four partitions in height painting, etc., complete.	S.ft.	135
28	Teakwood screen with double shutters, wooden panel, filling, fixed in floor, iron work and painting, etc., complete.	,,	84
29	Teakwood terminal finials	No.	4
30	Zinc storm water drain pipes 3″ dia. built into masonry.	R.ft.	112
31	Tarring wood work	Lump sum	
32	Providing Clerestories top and spirit room ...	Lump sum	
33	Clearing site and levelling ground and forming ramp in the side of verandah and spirit room.	Lump sum	

V. V. PATANKAR,
Executive Engineer.

MYSORE DIVISION.

Notice dated 19th December 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division up to 10th January 1928, for constructing a building for the New Police Station at Mandya. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the houre of 11 A.M. and 5 P.M., on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompained by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit